



NOTES:

1. All monuments shall use either $\frac{5}{8}$ inch \varnothing x 30 inches long iron rod or $\frac{3}{4}$ inch \varnothing x 30 inches long iron pipe.
2. All monuments shall be in accordance with the *Oregon Revised Statutes* Chapters 92 and 209.
3. Monument box shall be set within a 6 inch wide, round collar of 5,000 psi, high-early Portland Cement Concrete.
4. Place 3 - 2"x2" spacers, cut from 2" concrete patio block, evenly spaced to match finish grade.
5. For post-monumentation on existing concrete surfaces, core-drill or diamond saw-cut is required.



City Of Beaverton

**PUBLIC WORKS
DEPARTMENT**

**POST-CONSTRUCTION
CENTERLINE MONUMENTS**

CITY ENGINEER
Terry Waldele, P.E.

DATE
5 - 10 - 06

DRAWN BY
JR - CPD

DRAWING NO.
138